



# City of Cambridge

## PURCHASING DEPARTMENT

795 Massachusetts Ave. • Cambridge, Massachusetts 02139-3219

Amy L. Witts  
Purchasing Agent

**TO:** All Bidders

**FROM:** City of Cambridge

**DATE:** October 28, 2016

**RE:** File No. 7423 – Moore Youth Center Roof Replacement and Repair - Addendum No. 1

---

This addendum is comprised of:

1. Sign in sheet from pre-bid meeting (attached)
2. Bid opening and questions deadline extended
3. Changes to Drawing
4. Changes to Specifications
5. Questions and answers

The bid opening has been postponed from Thursday November 3, 2016 at 2:00PM to Monday November 7, 2016 at 2:00PM.

The questions deadline is extended from Friday October 28, 2016 no later than 11:00AM to Monday October 31, 2016 no later than 4:00PM.

### CHANGES TO DRAWINGS

1. Delete all references to “.060 EPDM adhered” & replace with “.090 EPDM adhered”.
2. On Drawing A2 South Elevation 4, delete note “New Alum. Casement Window to Match Existing Adjacent” and replace with “Demolish and legally dispose of existing louver and install new aluminum casement window. Install new steel protection/grating at window to match type at existing adjacent window”.
3. On Drawing A1 East Elevation 2, delete note “Remove Plastic Protection Glazing, Repair Trim & Paint Entire Window – Install New Plastic Protective Glazing” and replace with “Remove Plastic Protection Glazing, Remove Trim and Moldings and Replace with cellular PVC, Paint Entire Window, Install approved sealant at trim/molding to brick intersection, and Install New Plastic Protective Glazing”

**CHANGES TO SPECIFICATIONS**


1. Section 061063 Carpentry – Replace Paragraph 2.03 B, to read as follows:
  - B. Replacement wood trim shall be formed of exterior cellular PVC, with adhesive, fasteners, and concealment plugs as recommended by manufacturer.
2. Section 061063 Carpentry – Delete Paragraph 2.03 C.
3. Section 061063 Carpentry – Replace Paragraph 3.05 A, to read as follows:
  - A. Replace deteriorated wood trim & moldings with cellular PVC trim & moldings retaining the existing profiles and lines of construction. Fasten and secure all new cellular PVC trim & moldings as necessary to maintain weathertightness. Ease all transitions and edges. All fasteners shall be plugged with cellular PVC concealment plugs.

The following question was asked and answered:

**Question:** What the expected time of performance is on this project?

**Answer:** Substantial completion of the project is by December 30, 2016

All other details remain the same.



---

Amy L. Witts  
Purchasing Agent

Addendum No. 1

PRE-BID CONFERENCE SIGN IN SHEET

PROJECT: #7423 Moore Youth Center Roof Replacement and Repairs  
 DATE/TIME: Wednesday, October 26, 2016 at 10:00 AM  
 LOCATION: Moore Youth Center  
 12 GILMORE STREET, CAMBRIDGE, MA

NAME: <i>Robert Battelle</i>	COMPANY: <i>Crocker Architectural</i>	ADDRESS: <i>129 Southbridge Rd. N. Oxford MA</i>
PHONE NO.: <i>508-987-9900</i>	FAX NO.: <i>508-987-9900</i>	E-MAIL ADDRESS: <i>davis@crockerarchitectural.com</i>
NAME:	COMPANY:	ADDRESS:
PHONE NO.:	FAX NO.:	E-MAIL ADDRESS:
NAME:	COMPANY:	ADDRESS:
PHONE NO.:	FAX NO.:	E-MAIL ADDRESS:
NAME:	COMPANY:	ADDRESS:
PHONE NO.:	FAX NO.:	E-MAIL ADDRESS:
NAME:	COMPANY:	ADDRESS:
PHONE NO.:	FAX NO.:	E-MAIL ADDRESS: